

# MEG II実験液体キセノン検出器の インストール及びセンサー試験

→ 次のトークで


東大素セ 家城 佳、  
他 MEG II コラボレーション

# $\mu \rightarrow e\gamma$ search


Observation of  
lepton flavor violation (LFV)  
decay  $\mu \rightarrow e\gamma$

➔ Evidence of new physics!

e.g.  $\mu \rightarrow e\gamma$  with SUSY




New generation LFV experiments  
can explore the region predicted  
by BSM



# MEG II




900l  
LXe  $\gamma$  detector



Upgrades from MEG: { x2 beam rate  
x2 detector resolution and efficiency }  $\rightarrow$  x10 sensitivity  
( $4 \times 10^{-14}$ )


# LXe detector

- Measures the  $\left\{ \begin{array}{l} \text{energy} \\ \text{position of } \gamma\text{-rays.} \\ \text{timing} \end{array} \right.$
  - Readout: 2" PMTs  $\times$  668 + 12mm MPPCs  $\times$  4092
    - Granular & uniform coverage
    - x2 resolution improvement expected from MEG
- Energy resolution  $\sim 1\%$   
Position resolution  $\sim 2.5\text{mm}$




# Final stage of construction


Cabling



Closing the lid



Closing the flanges




last JPS (Mar2017)

# Installation & pipe connection

Installation




Pipe connection





# Filling LXe to the detector

1. Liquefaction (GXe storage tanks  $\rightarrow$  1000l LXe tank)
2. Vacuum evacuation of the detector (to  $\sim 2 \times 10^{-3}$  Pa)
3. Pre-cooling of the detector ( $\sim 175$ K)
4. LXe transfer from 1000l tank to the detector



# LXe transfer

View from a USB camera installed inside the detector




# Position monitoring

MPPC position was scanned with laser after installation ↓




However, inner cryostat deforms by heat shrink and LXe load.

→ Monitor the movement by position sensors




# Position monitoring

3 sensors are installed at 4 different position.






Moved mostly during the pre-cooling due to heat shrink. Result was roughly consistent with what we expect ( $\sim 1.6 \times 10^{-3} \text{ mm/m/K}$  heat shrink to bottom direction)




Cryostat is fixed at the bottom middle.

# X-ray survey





Position of the stage is measured by laser and monitored by laser and bubble level + camera.



# X-ray survey


Scan was performed in two directions in 1mm step.  
X-ray spot size ~ 2 mm x 30 mm



Event rate increase was successfully observed around X-ray irradiated region.  
Analysis is ongoing.

# LXe monitoring & control

We built a slow control system using special modules (SCS2000) developed at PSI



SCS2000 can:

- readout the sensors (bias & ADC)
- automatically or manually adjust the cooling power (refrigerators and LN<sub>2</sub>) by firmware
- allow users to monitor & control via internet

# LXe monitoring & control

Normal (stable) operation:


Temperature & pressure is maintained by adjusting electric heater power.

Emergency or special operation:

Open LN<sub>2</sub> valves for additional cooling



Firmware of SCS2000 does the control automatically.

- Heater power adjustment (PI control)
- LN<sub>2</sub> valve open at high temp. or high pres.
- Issue an alarm in case of emergency



# LXe monitoring & control

Overall system is monitored & controlled from web browser.




# Purification

Purity of Xe affects the scintillation  
(light yield, attenuation, pulse shape)

Two types of purifications are ongoing  
in parallel for ~2 months.




- Gas phase (getter)  
Slow (GXe ~35 l/min)  
Removes H<sub>2</sub>O, O<sub>2</sub>, CO, CO<sub>2</sub>, N<sub>2</sub>, H<sub>2</sub> ...
- Liquid phase (molecular sieve)  
Fast (LXe ~40 l/hour)  
Removes H<sub>2</sub>O




# Purification and detector stability

- Xe purity is improving (light yield increased  $\sim 10$  times over 2 month.)  
Currently the light yield is  $\sim 85\%$  of what we achieved in MEG.
- Temperature and pressure are sometimes unstable due to LXe purification pump trouble and due to heat income in LXe purification line.

→ Once we finish purification, the detector will be more stable.



# Status & schedule



- Construction & installation are finished!
- LXe operation started. Purification is ongoing.
- MPPC & PMTs are being tested → [Next talk \(S. Ogawa\)](#) with limited amount of DAQ channels available now (~1000ch)
- Detector monitoring is started → [Next next talk \(N. Matsuzawa\)](#)
- Pilot run will start in the end of 2017, followed by the engineering run and physics run in 2018.

# Summary

- LXe detector is successfully installed.
- Position of the detector is measured by wire sensors and X-ray.
- Slow control system is built. Purification is ongoing. (so far achieved ~85% of light yield in MEG)
- Commissioning of MPPC & PMTs is also ongoing.
- Monitoring of the detector is started.

} Next  
talks