Installation and test of the MEG Cockroft-Walton accelerator

Carlo Bemporad, Matteo Corbo, Nicolino Curalli, Marco Grassi, Peter-Raymond Kettle, Hiroaki Natori, Angela Papa, <u>Giovanni Signorelli</u>

PSI - INFN Pisa - ICEPP Tokyo

MEG Experiment Review Meeting July 18, 2007

Calibrations

• We are prepared for complementary and redundant calibration methods



The MEG C-W accelerator

- Y-ray production by the reactions $Li(p, \gamma)Be$ and $B(p, \gamma)C$
- Main method to check the energy scale and stability of the calorimeter on a daily basis

Reaction	Resonance energy	σ peak	γ-lines
Li(p, y)Be	440 keV	5 mb	17.6 MeV, 14.6 MeV
$B(p,\gamma)C$	163 keV	2 10 ⁻¹ mb	4.4 MeV, 11.7 MeV, 16.1 MeV

• LiF target is easier to prepare compared to Li alone but ¹⁹F has other lines

3





Machine Schedule

• We were almost on schedule with respect to what was shown at the february meeting

	Review 02/07	Present
Completion of manufacture	~ end-February 2007	end-February 2007
Acceptance Tests in Amersfoort NL with HVEE, INFN, PSI	~ mid-April 2007 ?	19-23 March 2007
Shipment to PSI	~ end-April ?	mid-May 2007
Machine Installation + Shipment/Guarantee Test	~ mid-April to mid-May 2007 ?	mid May to end June 2007





			May 2007			
Monday	Tuesday	Wednesday	Thursday	Friday	Saturday	Sunday
30	1	2	3	4	5	6
7	8	9	10	11	12	13
14	15	16	17	18	19	20
	22		24		26	
28		30	31	1		3

			June 2007			
Monday	Tuesday	Wednesday	Thursday	Friday	Saturday	Sunday
28		30	31	1		3
	5		7	8 10000 1000 10000	9	
11		13		15	Property for The All of the All	17
	19	20	21		23	
25		27		29	30	1



- Less than two months from the C-W delivery at PSI the proton accelerator and beam line are ready to enter into operation
- We are able to deliver protons to a target at the center of COBRA to generate 17.6 MeV calibration photons

Two-fold

- Installation and acceptance test
- Beam line towards COBRA



Cockroft-Walton area

- The new area was completed and equipped
- Classification as Accelerator facility: subject to rules from:
 - **BAG** Rules (Swiss Ministry of Health)
 - PSI Health Physics & Safety Rules
- Strict Rules governing:
 - Facility usage, operational personnel
 - "Schooling" of personnel, maintainance & upkeep...



Schweizerische Eidgenossenschaft Confederation suisse Confederazione Svizzena Confederazione svizzena

Sachverständige für den technischen Strahlenschutz

Titol	Herr
Name	Wernii Christian
Beruf	Physiker
Benerkung	Bevollmächtigter Sachverständiger für den Strahlen

Spezifikationen

1) Bewilligung für den	Betrieb der Beschleunigeranlagen un
Experimenten am Paul	Scherrer Institut (PSI) in Villigen
Tätigkeit	Betrieb
Zweck	Forschung, Wissenschaft
Gegenziand	Anlagen nach unten aufgeführter Liste

Diese Bewilligung umfasst folgende Anlage und Areale:

 Strahl im pi-E-5 Areal und im angrenzenden Areal mit den folg Protonen Energie: bis zu 1 MeV Strahlintensität: bis zu 1 uA

Certified Licence for Cockcroft-Walton Facility

up to Energy: Ι MeV Max. Current: Ι μΑ

Acceptance

Alignment	Current	Energy	
	Measurement with an Aluminum Faraday cup	Li(p, γ)Be line excitation on thick target (5 µm) + Nal absolute energy calibration	
The alignment was checked with the usage of a quartz crystal A most reliable, simple and sensitive method for beam tuning and diagnosis		$ \begin{array}{c} 18000 \\ strate{16000} \\ 514000 \\ 912000 \\ 011200 \\ 0$	
	Correlation of proprietary current meter and SCS2000 (nA!)	$\mu = (444 \pm 1) \text{ keV}$ $\Gamma = (6.8 \pm 0.5) \text{ keV}$	

9

Acceptance test summary

	Nominal	Measured at PSI
Terminal energy range	300 - 900 keV	200 - 1100 keV
Energy ripple	< 500 V _{rms}	< 50 V _{rms}
Angular divergence	< (5 x 5) mrad ²	~ (4 x 4) mrad ²
Spot size at 3 m	< (3 x 3) cm ²	< l cm ²
Energy setting reproducibility	0.1 %	ok
Energy stability FWHM	0.1 %	ok
Range of current	(Ι - Ι00) μA	(0.Ι -Ι35) μA
Current stability	3 %	ok
Current reproducibility	10 %	ok
Start-up time	< 20 min	< 15 min
\mathbf{V} where \mathbf{I} is the target (FOO \mathbf{I} is \mathbf{V})	< 2 µSv/hr @ I µA	< 0.1 µSv/h
A-ray level from the tank (500 kev)	< 5µSv/hr @ 100 µA	< 0.1 µSv/h @ 50 µA
	-	0.5* - 3** µSv/h @ I µA
A-ray level in the IIES area	-	Ι 4*** - 280* μSv/h @ 50 μA

> 60 keV, on the AI Faraday cup

> 10 keV, on the AI Faraday cup

> 60 keV, 3 cm from the beam line ***

Acceptance test summary

+++1/		
AC	CEPTANCE PRO	DTOCOL
1.0 MV SINGLE	TRON POSITIVE ION AG	CCELERATOR SYSTEM
P IN	Paul Scherrer Institute ref.: FN - Sez. di Pisa ref.: Pur. HVEE ref. B6759 & B	E 642950 order n.110 6760
Immediately after the succes accepted and the responsible will sign this acceptance pro	ssful completion of these tes e representatives of both buy ptocol.	ts at PSI the equipment will be ing parties INFN & PSI and Selle
Warranty as per contract.	29 June 2007 by con	tract!
Zürich, 1.9 june, 200	7.	
Carlo Ampl	Peter - Sugen Welle	American.
Drof C Dominiand	P-R Kettle	A W Ternstra

araday cup araday cup the beam line

Towards MEG area

- After this date we operated the machine by ourselves
- Successful mounting and operation of the proton beam line elements
 - beam shutter slits collimators straight insulated sections gate valves
- Integration with the experiment slow control (SCS2000 pressure, valve, currents, bellow system)
- Matching with the insertion system
 - we move 4 mm/s => need 10 minutes to insert the system (40 W)
 - to bo tested with the gas system in operation



Final Beam Line schematics

COBRA "edge" position



13

At COBRA edge

- With the magnetic field on we have to adjust the horizontal and vertical position of the beam
- Horizontal ~ I A, Vertical ~ 100 mA (few 10s G)

RED light = field ON



At COBRA center

~7 cm from the center

- We had a significant (~few cm) shift but with the help of dipoles and permanent magnets we could center the beam
- COBRA splits H⁺ and H₂⁺



At COBRA center

~7 cm from the center

- A larger beam spot is more suitable for our case
 - uniform target illumination
 - less target consumption for delivered current
- Defocussing using accelerator extraction voltage we obtain a ~ 2 cm beam spot



Beam spot measurement

- CW-source probe voltage changes the current
- CW-extraction voltage changes the focussing
- Camera picture through theodolite grid
 - Few mm at full focussing
 - ~ 2 cm at maximum CW defocussing





Centering and Focussing

- Some difference between COBRA off and COBRA on
 - Presence of stray fields
- Misalignment at COBRA of 2 mrad
- We have sufficient handles to compensate for this effect
- Usage of dipoles only
 - COBRA focuses the beam
 - Usage of C-W extraction voltage to defocus on target (to have a uniform distribution) at a sufficient level
 - We reserve the possibility to test the usage of a defocussing (!) quadrupole.
 - multiple scattering on thin foil
- ~I week test planned



Time needed for Calibration

- 10 minutes inserting
 - 10 minutes conditioning can go in parallel
- O(10 minutes) data taking at 30 Hz
 - 20k events
 - Rate (17.6 MeV) on LXe = $1.8 \text{ kHz} / \mu \text{A}$
- 10 minutes extracting
- Alpha-source and LEDs can be done during extraction/insertion



Daily operations	Periodic Operations	Rare Operations	
 -Automatic or Manual turn-on procedure -Optimization of source parameters -Calibration procedure (Bellows + Insertion System introduction into COBRA beam- shutter manipulation & reverse procedure) -Target (LiF) change when required 	Testing safety aspects (zone-interlocks etc.)	-Pressure SF6-vessel filling/emptying - N2 flushing + evacuation -Pressure-vessel opening/closing - Ion-source replacement - H2-bottle replacement -Intervention on internal parts	
Trained Shifters + assistant	Member of the "C-W Group" + assistant		

Conclusion and perspectives

- The system is ready to deliver the desired beam at the desired intensity to calibrate the LXe calorimeter
- No dangerous radiation (x-rays) to the area due to the choice of materials
- Few things need to be investigated
 - optimize optics w/all detectors inside
 - test the usage of a quadrupole
 - check target duration
 - the usage of the crystal has been of invaluable help but won't be possible at the center of COBRA in the final beamline configuration
 - multi-pixel target
 - ~ One week "C-W" beam time
- Full integration with PSI safety interlocks
- Some new pneumatic elements foreseen (intermediate crystal, FCup)
 - Test independently thanks to the separate C-W area

Back-up slides

Next slides are only intended for back-up use.

Centering procedure

Beam centering

- misalignment of 1.2 mrad in x, and in y
- small accelerator misalignment and long lever arm (10 m)
- presence of residual fields (iron platform, neighbouring areas, steering magnets off...) partially compensates or masks



Dipoles in operation

- cobra edge
- horizontal dipole at 0.3 V (=100 mA, ~ 20 Gauss) vertical 0.0 (residual fields on vertical magnet compensate y)



Switch COBRA on

- beam towards Berg
- Notice different camera position

RED light = field ON



Re-adjust horizontal dipole

- Horizontal dipole = 1.5 V
- Vertical = 0.1 V

RED light = field ON



At COBRA center

~7 cm from the center

- We had a significant (~few cm) shift but with the help of dipoles and permanent magnets we could center the beam
- COBRA splits H⁺ and H₂⁺



At COBRA center

- Defocussing using accelerator extraction voltage \bullet
- ~ 2 cm beam spot



"in-run" calibration

- It is possible to have a simultaneous µ & photon run
 - check of the gamma line behaviour in true experimental condition

29

- Not exactly at the center of the detector
- Also alpha-sources
 - trigger pulse shape discrimination
 - tested w/real trigger boards at the Pisa PMT test facility



X-rays from the C-W

- Proton Induced X-ray Emission
 - Each element emits caracteristics X-rays
 - Medical Physics, geology, etc...
 - small brehmsstrahlung background
- Independent p-current normalization
 - Nuclear reaction detected by dedicated hardware
- Sub-detector calibration
- Check of safe radiation level ok!
 - MEG TN041

Particle Induced X-ray Emission (PIXE) associated with the MEG Cockcroft-Walton

June 26, 2007

A. Baldini, C. Bemporad, F. Cei, M. Corbo, L. Galli, G. Gallucci, M. Grassi, D. Nicolò, A. Papa, G. Signorelli

INFN and University of Pisa

P-R. Kettle

Paul Scherrer Institut, Villigen







 σ_k

Transport simulation

Beam simulation with Transport

